

REVISION

#1 REVISED PER SITE PLAN
CHANGE 04 / 12 / 2002

#2 REVISED PER SITE PLAN
CHANGE 04 / 29 / 2002

#3 REVISED PER SITE PLAN
CHANGE 07 / 05 / 2002

#4 REVISED PER SITE PLAN
CHANGE 07 / 08 / 2002

╀╼┆┈┩╼┼╼┾╌╅┈╃╼┼╼┼╼┼┷┩┈╁┈╢╌╅┈┼╼┼┈╬╼┼╼┾╾┼

╼╁╼╪╌╄╼╃╌╃╼╂╼╁╌╬╼┦╼╂╼╏╌╂╴┼┈┧╌╁╌┨╌╧╸┠╌╅┈┾╾╏

WITKIN
DESIGN GROUP

LANDSCAPE
ARCHITECTURE
AND PLANNING

16853 N.E. 2ND AVENUE SUITE 401 NORTH MIAMI BEACH, FL. 33162 TEL 305-650-8669 FAX 305-650-9057


MEMBER: AMERICAN SOCIETY OF LANDSCAPE ARCHITECTS

All Ideas, designs, and indicated or represented by this drawing are used by and are the exclusive property of Witkin Design Group, Inc., and were created, evolved and developed for the use in and in conjunction with the project therein referenced. No such ideas, designs, and plans shall be used or disclosed to any person, firm or corporation for any purpose whatsoever without the written permission of Witkin Design Group, Inc.

DATE: 03/15/02

SCALE: 1" = 40' - 0"

DRAWING NO:



SITE TREE LIST

KEY	BOTANICAL & COMMON NAME	SPECIFICATIONS	QTY.
A SECOND	Conocarpus erectus*	12ft. ht., 6ft. spr., 4.5ft. C.T., 2.5in. D.B.H. cal. min.	21
	Green Buttonwood	Field grown	
	Quercus virginiana*	12ft. ht., 6ft. spr., 4.5ft. C.T., 2.5in. D.B.H. cal. min.	482
	Live Oak	Field grown	
5.752 2.053	Swietenia mahagoni*	12ft. ht., 6ft. spr., 4.5ft. C.T., 2.5in. D.B.H. cal. min.	604
	Mahogany	Field grown	1
	Bauhinia blakeana	10ft. ht., 4ft. spr., 2 in. D.B.H. cal. min.	27
\bigcirc	Hong Kong Orchid	Field grown	
*	Roystonea elata *	18-20ft. O.A. ht.	120
	Royal Palm	Field grown, Matched hts.	7
	Syragus romanzoffiana	14ft. O.A. ht.	12
	Queen Palm	Field grown, Matched hts.	
	Wodyetia bifurcata	14ft. O.A. ht.	125
0	Foxtail Palm	Field grown, Single Trunk, Matched hts.	

NOTES: 1. PLANS TAKE PRECEDENCE OVER PLANT LIST.

- 2. *-PLANT SPIECES THAT ARE NATIVE TO SOUTH FLORIDA AS OUTLINED BY THE SOUTH FL. WATER MANAGEMENT DIST. XERISCAPE PLANT GUIDE II.
- 3. PLANTS SHALL BE FLORIDA NO. 1 OR BETTER AS OUTLINED IN THE FLORIDA DEPARTMENT OF AGRICULTURE'S GRADES AND STANDARDS FOR
- 4. PLANTS SPECIFIED AS "MATCHED" SHALL BE SIMILAR IN HEIGHT,
- SHAPE AND FORM, NO EXCEPTIONS.
- 5. NO TREES SHALL BE LOCATED CLOSER THAN 10ft. TO SITE LIGHTING POLES OR 4ft. FROM UNDERGROUND UTILITY LINES.
- 6. NO LANDSCAPING SHALL BE PLANTED WITHIN 4ft. OF ANY FIRE HYDRANT, ALL FIRE DEPARMENT CONNECTIONS AND CHECK VALVE DEVICES.

SITE TREE REQUIREMENTS						
	SITE DATA	TREES REQ.	TREES PROV.			
STREET TREES	36,100 LF. TOTAL @ TREE PER 35 LF.	1012	1229*			
LOT TREES	266 DUELLINGS TOTAL @ 3 TREES PER LOT	798	798**			
ADDITIONAL SITE TREES	N/A	N/A	33***			

NOTES:

*ESTIMATED NUMBER OBTAINED BY CALCULATING TOTAL LINEAL STREET FRONTAGE (41,420 L. F.) AND SUBTRACTING STREET FRONTAGE AT FUTURE DRIVEWAYS (266 UNITS @ 20 L. F. EACH EQUALS 5320 L. F. OF DRIVEWAYS).

1810****

**NUMBER INCLUDES ESTIMATED AMOUNT OF LOT TREES PROVIDED FOR ENTIRE SITE BASED UPON TYPICAL UNIT LANDSCAPE PLANS ON SHEET L-4.

***NUMBER INCLUDES QUEEN PALMS (2:1) AND GREEN BUTTONWOOD TREES (1:1) INDICATED IN THE COMMON AREAS OF OVERALL SITE PLANTING PLAN.

****AS PER DADE COUNTY CODE, 18,100 SHRUBS SHALL BE PROVIDED (10 SHRUBS FOR EACH TREE REQUIRED)

#1 REVISED PER SITE PLAN CHANGE 04 / 12 / 2002 #2 REVISED PER SITE PLAN

CHANGE 04 / 29 / 2002 #3 REVISED PER SITE PLAN CHANGE 07 / 05 / 2002 #4 REVISED PER SITE PLAN CHANGE 07 / 08 / 2002

16853 N.E. 2ND AVENUE NORTH MIAMI BEACH, FL. 33162 TEL 305-650-8669 FAX 305-650-9057 MEMBER: AMERICAN SOCIETY OF LANDSCAPE ARCHITECTA


All ideas, designs, and indicated or represented by this drawing are owned by and

are the exclusive property of Witkin Design Group, Inc., and were created, evolved and developed for the use in and in conjunction with the project therein referenced. No such ideas, designs, and plans shall be used or disclosed to any person, firm or corporation for any purpose whatsoever without the written permission of Witkin Design Group, Inc. TITLE: LANDSCAPE PLAN ┍╏┩┩┍┡┋┋┩┩╃╒┋╇╇╒╒╇╒╒

┦╒╫╒┢╒┼╌┈═╏╌╧╌┾╌╃═╏┈┈┼╌┢┾╌╛╌╽╌╽╴┟┈╁╺

DATE: 03/15/02 SCALE: 1" = 40' - 0"

DRAWING NO:




QUANTITY	KEY	BOTANICAL / COMMON NAME	DESCRIPTION
1		Cordia sebestena GEIGER TREE	10' ht. X 5' spr.
1	ZW.	Phoenix roebelenii PYGMY DATE PALM	4' o. a. ht. 15 gal.
1	47 14	Tabebuia impetiginosa PURPLE TRUMPET TREE	12' ht. X 6' spr. f. g.
2	*	Veitchia montgomeryana MONTGOMERY PALM	16' o. a. matched hts. f. g.
16	AA	Agapanthus africanus LILY OF THE NILE	18" ht. X 18" spr. 3 gal.
5	АН	Allamanda cathartica 'Hendersonii Dwarf' DWARF ALLAMANDA	18" ht. X 18" spr. 3 gal.
19	CS	Conocarpus erectus 'Sericeus' SILVER BUTTONWOOD	24" ht. X 24" spr. 3 gal.
35	PL	Pentas lanceolata 'New Look Red' SHORT RED PENTAS	1 gal. full
AS REQ'D	LAWN	Stenotaphrum secundatum ST. AUGUSTINE GRASS	Solid Even Sod

LANDSCAPE LEC Ordinance 98-1		
ZONE DISTRICT: RU-IM (a)	· · · · · · · · · · · · · · · · · · ·	
Gross Land: 5000 (s. f.) Net Land: 5000 (s. f.)	Water Boo	dies: 0
	REQ.	PROV.
Landscape Open Space (if applicable) Greenbelt Width (if applicable) Lawn Area (As defined in Ordinance)	N/A N/A 35%	N/A N/A 35%
TREES:	3	
Trees per Net Lot: Note: 30% of required trees and/or palms shall be native species. Street Trees:	1*	3 1 (separate plan*)
TOTAL NUMBER OF TREES	4	4
SHRUBS: (10 shrubs for each tree req.)	40	40
30% shrubs/hedge shall be native species. Irrigation system required pursuant to Chapter 33 Da	ade County	<u></u>

PROPOSED 60 ACRE P.A.D.

FOR G.C. HOMES, INCORPORATED

NMIAMI DADE COUNTY FLORIDA




TITLE: TYPICAL UNIT
LANDSCAPE PLAN

DATE: 03/15/02

SCALE: 1" = 10' - 0"

DRAWING NO:



LARGE TREE PLANTING DETAIL

SMALL TREE PLANTING DETAIL


BACKFILL SOIL

OF ROOT BALL


PLANT BALL

EXISTING SUBSOIL


REMOVE BURLAP FROM TOP




TYPICAL TREE GUYING DETAIL




STRAIGHT TRUNK PALM PLANTING DETAIL






TYPICAL SHRUB PLANTING DETAIL



TYPICAL GROUND COVER PLANTING DETAIL



.

PLANTING NOTES:

(See plant specification and details for additional standards)

-All plant material is to be Florida Number 1 or better pursuant to the Florida Department of Agriculture's Grades and Standards for Nursery Plants.

-Sod is to be grade "A" weed free.

-All areas marked "LAWN" shall be solid sodded with St. Augustine "Floratam" solid sod. See limit on plan. All areas marked 'Bahia Grass' shall be solid sodded with Paspelium

notatum. All sod is to be laid level, tight, and cut even along planting beds.

-All plants are to be top dressed with a minimum 3" layer of Melaleuca mulch,

Eucalyptus mulch or equal.

-Planting plans shall take precedence over plant list in case of discrepancies.

-No changes are to be made without the prior consent of the Landscape Architect and Owner. Additions and / or deletions to the plant material must be approved by the project engineer.

-Landscape Contractor is responsible for providing their own square footage takeoffs and field verifications for 100% sod coverage for all areas specified.

- All landscape areas that are to be provided with an automatic sprinkler system will provide 100% coverage, and 50% overlap, as per Chapter 33 of Miami- Dade County Code.

- All trees in lawn areas are to receive a 24" diameter mulched saucer at the base of the trunk.

- All lawn located in parking islands is to be set flush with top of curb. Provide adequate soil to within 3" of top of curb.

- Trees are to be planted within parking islands after soil is brought up to grade. Deeply set root balls are not acceptable.

 Planting soil for topsoil and backfill shall be 50/50 mix, nematode free by Morris Magic soil, Hialeah, Florida. Planting soil for annual beds to be comprised of 50% Canadian peat moss, 25% salt free coarse sand and 25% Aerolite.

- Tree and shrub pits will be supplemented with "Agriform Pells", 21 gram size with a 20-10-5 analysis, or substitute application accepted by Landscape Architect. Deliver in manufacturer's standard containers showing weight, analysis and name of manufacturer.


GENERAL NOTES:

-The Landscape Contractor is to locate and verify all underground and overhead utilities prior to beginning work. Contact proper utility companies and / or General Contractor prior to digging for field verification. The Owner and the Landscape Architect shall not be responsible for any damages to utility or irrigation lines (see Roadway Plans for more utility notes).

-Landscape Contractor is to verify all current drawings and check for discrepancies and bring to the attention of the Landscape Architect prior to commencing with the work.

-All unattended and unplanted tree pits are to be properly barricaded and flagged during

-All planting plans are issued as directives for site layout. Any deviations, site changes, et cetera are to be brought to the attention of the Landscape Architect for clarification prior to installation.



TITLE: LANDSCAPE DETAILS

╶╸┩┋

المناز مراجعات برواد فالمنصب والمراجعة والمحاجب والمحاجب والمناور والمنطوعة والمتارك فالمتارك والمتارك والمتارك

REVISION

DATE: 03/15/02

SCALE: NOT TO SCALE

DRAWING NO: